



GA Building Projects

18 Disa Street, Milnerton
Cape Town 072 853 5677

info@gabuildingprojects.com
www.gabuildingprojects.com

Boundary Wall

Item	Description	QTY	Unit	Unit Price	Price	Completed
Excavation						
1	Dig trench 750mm x 500mm. Widening at columns for pad foundations 1000mm x 1000mm. Additional charge for trench deeper than 500mm.	20	m	400	8,000	
				Total:	8,000	
Wetworks						
1	Cast 30Mpa concrete foundations. Rebar Y12 in concrete.	20.0	m	960	19,200	
2	Build foundation walls. Brick force every course. 3 courses. Filled with concrete. ROK clay bricks.	20.0	m	500	10,000	
3	Build new 230mm walls and columns with ROK clay bricks.	36.0	m2	1,350	48,600	
4	Columns to be filled with Rebar Y12 and filled with 25Mpa concrete.	12.0	Unit	600	7,200	
5	Plaster new internal and external brickwork.	1.0	Unit	23,500	23,500	
6	Install capping decoration. Supplied by client.	1.0	Unit	3,800	3,800	
				Total:	112,300	
General						
1	Remove rubble.	2	Unit	1,900	3,800	
				Total:	3,800	
Office						
1	Sanitation, transportation and administration	7.0	%	124,100	8,687	
				Total office:	8,687	

Total Proposal: R132,787